



Always check the website for the most updated specifications: www.americh.com



Tub pictured with optional waste & overflow









**Builder Series** 

**Platinum Series** 


**Luxury Series** 




Combination (pump and blower location only)



Airbath System II



Airbath System III



# **INSTALLATION TIPS**

- Install according to Owner's Manual and local codes.
- Airbath III units may be 11/2" 21/2" higher than stated.
- Any whirlpool or Airbath<sup>®</sup> unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.
- Cut-out dimensions: Americh recommends waiting until the actual unit is received or contact us for a template.

#### **DIMENSIONS**

60" diameter x 21" ( 1524 mm dia. x 533 mm) Whirlpool Operating Gallons = 60 (Liters = 227) Gallon to Overflow = 86 (Liters = 325)

TUB FLOOR: Textured

**UNDERMOUNT:** Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- Always take dimensions directly from the unit.

### **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

## **OPTIONAL ACCESSORIES**

- Chromotherapy
- Grab Rail
- High Density Insulation<sup>\*</sup>
- Inline Heater
- Jets: Additional or Rotary<sup>\*</sup>
- Pillows: 13"\*
- Quiet Pump with Built-in Heater Upgrade\*
- Remote Control Upgrade (Select Series Only)
- Trim Kit Upgrade<sup>1</sup>
- Waste & Overflow
- \*Standard on Platinum Series

# **CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79

Contact Americh for additional approvals.