






Always check the website for the most updated specifications: www.americh.com










Tub pictured with optional waste & overflow.

·

Builder Series








Platinum Series

Combination

(pump and blower location only)






Airbath System III Airbath System III







INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.

DIMENSIONS

60" x 30" x 22" ($1524 \times 762 \times 559 \text{ mm}$) Whirlpool Operating Gallons = 40 (Liters = 152)Gallon to Overflow = 65 (Liters = 246)

TUB FLOOR: Non-Textured

UNDERMOUNT: No

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

STANDARD EQUIPMENT:

- Apron
- Molded Tile Flange

OPTIONAL ACCESSORIES

- Chromotherapy*
- Grab Bars: 9" * 14" 16"
- High Density Insulation*
- Inline Heater
- Jets: Additional or Rotary
- Pillows: 13"
- Quiet Pump with Built-in Heater Upgrade*
- Remote Control Upgrade (Select Series Only)
- Trim Kit Upgrade^{*}
- Waste & Overflow^{*}

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8

Contact Americh for additional approvals.

^{*}Standard on Platinum Series