






Always check the website for the most updated specifications: www.americh.com










Tub pictured with optional waste & overflow.

All bathtub dimensions are  $\pm 1/2$ ".

## **Builder Series**

# **Luxury Series**






## Platinum Series


## Combination

(pump and blower location only)






# Airbath System II Airbath System III







#### **INSTALLATION TIPS**

- Install according to Owner's Manual and local codes.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.

#### **DIMENSIONS**

60" x 30" x 22" ( 1524 x 762 x 559 mm) Whirlpool Operating Gallons = 40 (Liters = 152) Gallon to Overflow = 65 (Liters = 246)

TUB FLOOR: Non-Textured

**UNDERMOUNT: No.** 

## **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

#### **STANDARD EQUIPMENT:**

- Apron
- Molded Tile Flange

#### **OPTIONAL ACCESSORIES**

- Chromotherapy\*
- Grab Bars: 9" \* 14" 16"
- High Density Insulation\*
- Inline Heater
- Jets: Additional or Rotary\*
- Pillows: 13"
- Quiet Pump with Built-in Heater Upgrade\*
- Remote Control Upgrade (Select Series Only)
- Trim Kit Upgrade<sup>2</sup>
- Waste & Overflow<sup>\*</sup>

#### **CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8

Contact Americh for additional approvals.

<sup>\*</sup>Standard on Platinum Series